



Norwich Pavilion

Bid Addendum 4

Issue Date – 11/2/2018

To All Bidders:

This addendum amends or supplements the original specifications, related documents, and previous addendums for this project. Please include a copy of this addendum with your bid submission to prove receipt of Addendum No.4 and its terms.

Issued herewith are the following items:

The following changes have been made to the specifications:

ITEM 1: Volume I, Proposal Affidavit has been added

List of Contractor RFIs

ITEM 2: See enclosed RFI Log

This amendment shall be considered in submitting your bid and shall be attached to the bid proposal and made a part thereof.

PROPOSAL AFFIDAVIT

(To be filled in and executed if Contractor is a Corporation)

State of _____)

ss:

County of _____)

_____, being duly sworn, deposes and says that he/she is Secretary of _____, a corporation organized and existing under and by virtue of the laws of the State of _____, and having its principal office at:

Number and Street

City

County

State

Affiant further says that he/she is familiar with the records, minutes, books and by-laws of

Name of corporation

Affiant further says that _____
Name of officer of the corporation

_____, is duly authorized to sign the proposal for
Title

for said corporation by virtue of

(State whether a provision of by-laws or a resolution of the Board of Directors. If by resolution, give date of adoption).

Affiant

PROPOSAL AFFIDAVIT (Continued)

Sworn to before me and subscribed in my presence this _____ day of _____, 2018.

Notary Public


County State

My Commission expires:

Date

Norwich Pavilion

RFI Log

Item	Date Initiated	Discipline	Description	Reply
1	10/29/18		Section 321400 page 3 or 6- States 50 year warranty on all wood. He said this is not something that most companies can offer.	Wood Warranty to be 5 years
2	10/29/18		Paint Specs and finish schedule for what gets painted.	All visible framing and plywood is to receive 1 coat of primer, and 2 coats of paint. Paint and Primer is to be water based acrylic alkyd, semi-gloss finish. Sherwin Williams, or equal. Exact white color TBD. Allow treated lumber to dry as required by the paint manufacturer prior to priming and painting.
3	10/29/18		Is the service a single phase or three phase?	Single Phase
4	10/29/18		Coded note 4 on L-501 calls out for a total of 16 receptacles. However, there are only 8 shown on the plan. Where are the remaining 8 receptacles to be located?	8 receptacles are shown on the plan and the other 8 are on the H Frame Panel.
Addendum No. 3 Issued 10/30/2018				
5	11/01/18		Note #8 on Sheet A-101 indicates that we are to use 5/8" treated plywood roof sheathing and to also "provide manufacturer's approved roofing fasteners at a length so as to not become exposed on the underside of the plywood decking..." The manufacturer's recommended nail length for standard asphalt shingles is 1" and on dimensional shingles it's 1-1/4", therefore, there is no way to achieve this request. How shall we proceed?	Roof deck, shingles, and fasteners are to remain as designed, and as per the manufacturer. Before painting the underside of the deck, loose splintering wood is to be removed from sheathing prior to priming. Visual inspection after priming is required before proceeding with two coats of paint.
6	11/01/18		Is Norwich Twp. submitting and paying for the General Building Permit? Which jurisdiction does this fall in for inspections?	This will be done through the City of Hilliard and we will not be charged (the pavilion will be donated to the City after completion).
7	11/01/18		Can you tell me what the existing light poles (L-1) the City has in stock are so we can match it? Model #?	 <p>The image above shows the fixture to match. The exact model and manufacturer will be supplied post bid, when available.</p>
8	11/2/2018		Aggregate- Information on page 4 & 5, section 32 13 13 is sourced from out of the state, and it is costly.	The intent of this project is to use standard aggregates that exist in standard concrete mixes. The aggregates mentioned below were for a finish that was not specified in this project.
Addendum No. 4 Issued 11/2/2018				